SECTION 617 HAULING

617.1 Description

(1) This section describes transporting materials from the point of supply to the work site.

617.2 (Vacant)

617.3 Construction

(1) Haul materials from the pit, crushing plant, quarry, railroad car, or other material source to the work site in an engineer-approved vehicle. The engineer may approve any size or type of vehicle for hauling provided that vehicle conforms to the following:

1. Applicable legal restrictions imposed by other jurisdictions as specified in 107.1.
2. For material specified for measurement by volume in the vehicle, the provisions of 109.1.3.

(2) Conform to additional hauling requirements specified under the individual bid items for the material being hauled.

(3) Unless the contract specifies otherwise, build and maintain private roads, bridges, culverts, and structures as necessary to reach the work site from the material source. Also, maintain, repair, and restore previously constructed private roads, bridges, culverts, and structures used to pre-hauling condition.

617.4 Measurement

(1) The department will measure the Hauling bid items by the cubic yard mile acceptably completed. The department will determine the total quantity for payment by multiplying the number of cubic yards hauled and placed in each zone by the mile number of the zone. The department will determine mile zones along the shortest and most practical line of haul from the loading point to and along the project. The department will only measure hauling of materials specifically included in a Hauling bid item.

617.5 Payment

(1) The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
617.0100	Hauling (material)	CYMI

(2) Payment for the Hauling bid items is full compensation for hauling the specified materials and, unless the contract specifies otherwise, costs associated with private roads, bridges, culverts, and structures used to haul material under this bid item.

(3) If the contract does not include the Hauling bid item, all hauling is incidental to the related work. Hauling materials not specifically included in a Hauling bid item is also incidental to related work.