SECTION 619 MOBILIZATION

619.1 Description

(1) This section describes the work and operations necessary to move personnel, equipment, supplies, and incidentals to the project site and to establish all of the contractor's offices, buildings, sanitary accommodations, and other facilities necessary to work on the project. It also includes all other work and operations whose performance is required, or for costs necessarily incurred before beginning work on various items on the project site.

619.2 (Vacant)

619.3 (Vacant)

619.4 Measurement

(1) The department will measure Mobilization as each individual unit acceptably completed.

619.5 Payment

(1) The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
619.1000	Mobilization	EACH

(2) Payment for Mobilization is full compensation for supplying and providing all materials, facilities, and services, and for performing all work necessary to complete this contract bid item.

(3) The department will prorate payment for Mobilization up to 10 percent of the original contact amount with payments made at 5, 25, 50, and 75 percent of contract completion with the balance in excess of 10 percent of the original contract amount payable upon 90 percent completion. The department will calculate individual payments using department form WS6191 available at:

http://roadwaystandards.dot.wi.gov/standards/forms/ws6191.xls

(4) If the contract does not include a separate Mobilization bid item, the work necessary for mobilization is incidental to work included under other contract bid items.